



MAIN BUILDING NORTH WING DEMOLITION

September 9, 2014

Pro-Green Demolition Ltd. has been retained by the London Health Sciences Centre to complete the asbestos abatement and demolition of the former South Street Campus hospital Phase A buildings, located on the south side of South Street, in London, Ontario. The abatement and demolition work commenced in early January and is slated for completion by December 2014. The Ministry of Labour Notice of Project No. for this project is 13eN153642 and the City of London Demolition Permit number is 14 001875 000 00 DM.

Together with the consulting team (AECOM and Pinchin), Pro-Green has developed the safest possible asbestos abatement procedures to remove the asbestos from the buildings prior to demolition. One of the unique procedures of this project is that during the demolition of the North Wing of the Main Building, pedestrians and local residents in the vicinity may be able to see our abatement workers. Pro-Green's workers will be wearing respirators and disposable coveralls for their protection during the Building 65 North demolition, as a small amount of the asbestos contained in the wall plaster in the building cannot be practically removed prior to demolishing this building.

Ministry of Labour Consultation

Consultation with the Ministry of Labour was undertaken related to the North Wing demolition. The Project Team met with the Ministry of Labour (Laurie Wheeler-CIH-Hygiene Consultant and Chris Dama-Occupational Health & Safety Officer) in April to review the asbestos building demolition procedure for the former Thameswood Lodge to ensure that it was in compliance with applicable regulatory requirements. The same demolition approach used for the Thameswood Lodge will be used for the North Wing. As such, the workers on this specific demolition task are working to a specific work procedure that protects both them and the public at large in accordance with applicable regulatory requirements.

Additional Procedures to Protect the Workers and Public During the North Wing Demolition

All required interior asbestos and hazardous material abatement procedures were completed prior to structural demolition of the North Wing.

During structural demolition, amended water (water with a wetting agent or surfactant added) will be applied on a continuous basis over the entire North Wing to minimize dust during demolition. Further, Pinchin will be performing ambient air quality sampling and analysis to ensure that the water misting dust mitigation measure is effective. The east and north walls of the North Wing will be the last structures to be demolished (providing a wind and noise break to the local residents) and there will be no demolition work undertaken on days with excessive winds. The demolition of the North Wing of the Main Building is anticipated to be completed in approximately ten days.

Any further questions regarding the demolition procedures for the North Wing can be directed to the London Health Sciences Centre Phase A Decommissioning Hotline number: **519-685-8383**